
ENGINEERING PHARMACEUTICAL INNOVATION



Controlled Environment Commissioning and Qualification "Using a Phased Approach to meet schedule demands"

Michael Marino, Sr. QE

Scientific



Effectively Integrating C&Q with Construction & Startup Activities

- WHY ?? ...(the usual suspects)
 - Construction delays; delivery issues; punchlists not completed
 - Manufacturing startup dates get pulled in due to operations or product related issues, validation runs etc.

Results...

- Commissioning and Qualification timelines usually get compressed (aka "SQUEEZED")
- This program outlines a phased approach to Cleanroom and Utilities Qualification while maintaining Quality and Regulatory requirements <u>plus</u> meet the plant's business requirements

SPE

NGINEERING PHARMACEUTICAL INNOVATIO







- Intent is to develop a Controlled Environment and critical utility Qualification Strategy that allows manufacturing lines to be installed, validated, and begin Human-Use product builds
- Using this strategy we can document and execute a logical and defendable Qualification Plan to commission, certify, & qualify CE's and systems as construction and startup is completed

SPI

ENGINEERING PHARMACEUTICAL INNOVATION

 Ultimate goal of this phased approach is to accommodate an expected "staggered" manufacturing





- For Commissioning:
 - Complete and approve a "Design Intent Document" (DID)
 - Develop commissioning plans that will incorporate a segregated approach
 > HVAC systems
 - BAS / Central Monitoring system
 - >CDA
 - ➤ High Purity water
 - Integrate commissioning early in the construction schedule
 - Have document formats agreed to up front


ISPE

ENGINEERING PHARMACEUTICAL INNOVATION























Qualification Requirements (cont.)

OQ testing – CE (at-rest / in-operation)

- SOP's approved (Cleaning; PM; EM)
- Microbial Sampling Plan (Airborne, Surface & Water)
- · Process equipment moved in and connected
- OQ duration 24 hour / 5 Day operational (functional) tests
 - Temperature trends -(can use chart recorders for data)
 - Humidity trends- (chart recorders for data)
 - DP trends (manual documentation during test period)
 - CMS action limit alarm tests (if applicable)
- Deviations remediated
- OQ summary report approved

CE & systems released for Process Validation runs (NOTE: product is NOT for human use applications at this stage)

ENGINEEDING PHARMACEUTICAL INNOVATI



Qualification Requirements (cont.)


PQ testing – CE (in-operation - routine)

- PQ duration (to prove repeatability) min 2-3 manufacturing weeks
- SOP's approved (Cleaning; PM; EM)
- Microbial Sampling Plan (Under Routine Monitoring)
- Manufacturing Line running in-human use product
- Subsequent Equipment Move in and connections
- PQ summary report approved

Cleanroom and systems released for in-human use manufacturing

SP

SINFERING PHARMACEUTICAL INNOVATION



Qualification Requirements- Additional Manufacturing Equipment Moves

- Manufacturing line 2,(N) install in CE
 - Create Change Control documents
 - Amend Sampling Plan drawing
 - ➤ Cleaning SOP's
 - Amend Layout drawing
 - Generate new PQ protocol for CE testing
 - > Additional EM monitoring to new line (plus existing)
 - Temperature / Humidity Data (during install and startup of new line)
 - DP Data (during install and startup)
 - > Existing product builds are "at-risk" and go on hold
 - > Generate and Approve new line PQ summary report

ENGINEERING PHARMACEUTICAL INNOVAT

SP



